**CENTRAL WAREHOUSING CORPORATION**
**(A GOVT. OF INDIA UNDERTAKING)**

**No.CWC/RO-JPR/NIQ/Deoli/2019-20/** **Date: 10.07.2019**

## NOTICE INVITING QUOTATION

Sealed percentage rate quotations are invited from the interested experienced contractors having valid GST registration who had never been blacklisted / debarred by any of the Govt. Department/ Govt. Organization / Central PSUs/ State PSUs in last 5 years.

| Sr.No. | NIQ NO. | Name of Work | Estimated cost put to NIQ | Earnest Money | Time allowed for Completion of work | Last date and time for downloading of NIQ | Last date and time of submission of Quotation | Date and time of opening of Quotation |
|---|---|---|---|---|---|---|---|---|
| **1.** | CWC/RO-JPR/NIQ/Deoli/2019-20 dated 09.07.2019 | Pre-Monsoon repair for the year 2019-20 at CW, Deoli (Raj) | **Rs. 62,823.91** | **Rs. 1,300/-** | **15 Days** | **16.07.2019 Upto 16:00 Hrs.** | **17.07.2019 Upto 15:00 Hrs.** | **17.07.2019 at 15:30 Hrs.** |

The quotation documents along with terms & conditions and schedule of work can be downloaded from websites **www.cewacor.nic.in, http://eprocure.gov.in/epublish/app & www.tenderhome.com**
**Upto 16.00 Hrs. on 16.07.2019**

Duly filled in quotation along with self-attested copies of experience certificate, valid GST registration, PAN card & **EMD** of Rs.1,300/- in form of Demand Draft in favour of **RM, CENTRAL WAREHOUSING CORPORATION** payable at Jaipur, in sealed envelope super scribing the name of the work thereon shall be submitted to the office of **The Regional Manager, Central Warehousing Corporation, Regional office, A-25, Sidharth House, Tilak Marg, C-Scheme, opp. Udyog Bhawan, Jaipur-302005 (Raj.)** up to **15.00 hours** on **17.07.2019** and the same will be opened **at 15.30 hrs**. On the same day in the presence of Quotationers/ contractors who may wish to be present at the time of opening.

**The quotation received without EMD shall be summarily rejected. There is no EMD exemption on account of MSME**

**Eligibility Criteria**: Quotationers should have completed successfully at least **one** similar nature of work "(i.e. construction /repair of godowns/ building works/Industrial shed) of value not less than Rs. 21,989/- (35% of the Estimated Cost) during the last **four** financial years (i.e., 2016-17, 2017-18, 2018-19 & Current year 2019-20) up to the date of quotation submission.

**Note: It should be noted that credentials for the works executed for private organization shall not be considered.**

The Central Warehousing Corporation reserves the right to accept or reject all/ any part of quotation without assigning any reason there-of.

**EXECUTIVE ENGINEER**

Copy to:

1. The SAM (A/cs) /Accountant (Engg Section), CWC, RO, Jaipur.
2. The Warehouse Manager, CW, Sikar (Raj.)
3. Notice Board of RO, Jaipur / CW, Sikar (Raj.)
4. CWC working contractors

**CENTRAL WAREHOUSING CORPORATION**
**(A GOVT. OF INDIA UNDERTAKING)**

**Name of work:** Pre-Monsoon repair for the year 2019-20 at CW, Deoli (Raj)

## Schedule of Quantity

| Sl No | Description of Item | QTY | UNIT | RATE | AMOUNT |
|---|---|---|---|---|---|
| 1 | Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : In 75x75 mm deep chase | 95.20 | Metre | 153.00 | 14565.60 |
| 2 | Plugging roof leakage in AC sheets by providing and applying bitumen compound of approved quality on 'J' hook bolts with tightening of J hooks wherever necessary including providing and fixing G.I. bitumen washers wherever necessary as per instructions of engineer in charge | 1508.02 | Sqm | 3.50 | 5278.07 |
| 3 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in – charge: Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) | 0.54 | Cum | 997.05 | 538.41 |
| 4 | Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: Asbestos sheet | 44.37 | Sqm | 32.85 | 1457.55 |
| 5 | Supplying & Laying saturated felt type 3 grade-I (Hessain base) on top of AC Ridges with suitable blows type petroleum bitumen of penetration of IS grade 85/25 of approved quality by apply 1.45 Kg. per Sqm. (The hessain type tarfelt should be of approved quality and conform to IS 1322) | 125.09 | Sqm | 198.65 | 24849.13 |
| 6 | Providing asbestos cement 6mm thick corrugated sheets roofing and fixing with g.i. j or l hooks, bolts and nuts 8 mm dia g.i. plain and bitumen washers complete (excluding cost of purlins, rafters and trusses) corrugated sheets upto 60 pitch (with one and half corrugations overlaps). | 44.37 | Sqm | 363.65 | 16135.15 |
| | **Estimated Cost ( item no 1 to 06) Rs.** | | | | **62,823.91** |

(Rupee Sixty Two Thousand Eight Hundred Twenty Three and Paisa Ninety One)

Credit Value:

| Sl No | Description of Item | QTY | UNIT | RATE | AMOUNT |
|---|---|---|---|---|---|
| 1 | AC sheets of size | | | | |
| a) | 3.05x1.05 m | 17.00 | Each | 8.00 | 136.00 |
| | | | | **Total Rs.** | **136.00** |

(Rupees One Hundred Thirty Six only)

**EXECUTIVE ENGINEER**

**TERMS & CONDITIONS:**

1) Works should be executed as per CPWD specifications.
2) Copy of self-attested PAN CARD, Experience Certificate & GST Registration along with quotation / tender document shall be submitted
3) All T&P, Water & Electricity required for the work will be arranged by the contractor at his own cost.
4) In the event of any of the documents found fabricated / forged / tampered / altered / manipulated in the NIQ, then the EMD of the contractor would be forfeited and he would be debarred for participating in CWC – tendering for 5 years.
5) The party to whom the work will be awarded will execute a formal agreement with CWC on a non-judicial stamp paper of appropriate value.
6) The rate quoted to be remain valid for **60(Sixty)** days w.e.f. date of opening of bid.
7) Time allowed for completion of work is **15 Days** from the date as mentioned in the work order.
8) The rates are inclusive all lead & lifts etc.
9) All taxes Income Tax, Work Tax etc. (except GST) as applicable will be deducted as per Govt. Rule from the contractor bill and payment will be released through e-payment by RO, Jaipur.
10) **10% Security Deposit will be deducted from the gross bill amount & will be released after the defect liability period of six month which will be reckoned from the date of successful completion of the work. In case any defect is found within the defect liability period, the same shall be repaired by the contractor immediately at his own cost.**
11) The rates quoted by the Tenderers/contractors shall be inclusive of GST or all applicable taxes, Building and other Construction Workers Welfare Cess, levies, duties on materials or services and on complete works in respect of this contract shall be payable by the contactor and Central Warehousing Corporation will not entertain any claim whatsoever in this respect. This should be included in the rates quoted by the contractor
    i) However, contractor is required to submit tax invoice as per rules under GST law
    ii) CWC shall deduct GST at source at applicable rates in case transactions under this contract are liable to GST deduction at source.
    iii) Under GST regime, the contractor is required to correctly and timely disclose the details of output supply to GST as per GST rules in his GST return. Non-compliance would result in mis-matching of claims and denial of input tax credit to CWC. Notwithstanding, anything contained in the agreement/contract in case of such default by the contractor, the amount of input tax credit denied in GST along with interest and penalty shall be recovered from the contractor.
    iv) Unless expressly stated, otherwise, where any identifiable cost saving are realized during the currency of contract by virtue of deduction:
        a) In rate of tax on supply of goods and services.
        b) Any benefit of input tax credit accrued to the contractor, contactor shall be passed on such benefit to CWC by way of commensurate reduction in prices.
12) Contractor will be fully responsible to labor payments, accident, mishappening, damages & other labor welfare & safety measures.
13) The above shown quantities are tentative & may vary as per site condition..
14) GST or any other tax on input material or services used by contractor in respect of this contract shall be payable by the contactor and Central Warehousing Corporation will not entertain any claim whatsoever in this respect.
15) The rates quoted by the Tenderers/contractors shall be inclusive of GST/all applicable taxes, Building and other Construction Workers Welfare Cess, levies, duties on materials or services and on complete works in respect of this contract shall be payable by the contactor and Central Warehousing Corporation will not entertain any claim whatsoever in this respect.
16) The voucher of Cement & Bitumen should be produced while submitting the bills.
17) The contractor shall procure Portland Pozzolana Cement (PPC) as per IS-1489 Part-I in all the works except Cement Concrete pavement works wherein Ordinary Portland Cement (OPC) of grade 43 (as per IS:8112) and /or 53 grade (as per IS:12269) shall be used

**EXECUTIVE ENGINEER**

**SIGNATURE OF CONTRACTOR**

**CENTRAL WAREHOUSING CORPORATION**
**(A GOVT. OF INDIA UNDERTAKING)**

**NAME OF WORK:** Pre-Monsoon repair for the year 2019-20 at CW, Deoli (Raj)

**Estimated cost from item No.01 to 06 is Rs. 62,823.91 (Rupee Sixty Two Thousand Eight Hundred Twenty Three and Paisa Ninety One)**

a) I/We hereby tender our rates as_____%

(_____percent)

**ABOVE** the rates entered in the schedule of quantities from item No. 01 to 06.

OR

b) I/We hereby tender our rates as _____%

(_____percent)

**BELOW** the rates entered in the schedule of quantities from item No. 01 to 06.

Note: 1.Quotationers should quote their percentage appropriately either at (a) or (b) as the case may be.

2. No enhancement or abatement is applicable for credit value item.

**EXECUTIVE ENGINEER**

**SIGNATURE OF CONTRACTOR**