

**CENTRAL WAREHOUSING CORPORATION
(A GOVT. OF INDIA UNDERTAKING)**



**CONSTRUCTION CELL
NEW MARKET COMPLEX
CMC BUILDING (6TH FLOOR)
15N, NELLIE SENGUPTA SARANI
KOLKATA-700 087**

No.CWC/CC-KoI/NIQ-(E)/C.K.Road/2015-16/

Date: **25.01.2016**

NOTICE INVITING QUOTATION

NAME OF WORK : Electrical Renovation work at CW, C.K.Road for the year 2015-16

Sealed percentage rate quotations are invited from the interested electrical contractors who had never been blacklisted /debarred by any of the Govt. Department/Govt.Organization /Central PSUs/State PSU and who will submit an undertaking at "**Annexure A**" attached at **Page No.8** and should have completed similar nature of electrical work in Govt. Department /Public Sector Undertaking/Govt. Construction Agency during last seven years. A list of the completed work be enclosed with filled quotation supported with performance/ completion certificate. Contractor should have valid electrical license and self attested copy of the same must be submitted with the quotation.

The quotation papers may be had from the office of the EXECUTIVE ENGINEER, CENTRAL WAREHOUSING CORPORATION, New Market Complex, CMC Building(6th floor),15N,Nellie Sen gupta Sarani,Kolkata-700087 **free of cost** in working hours from 10.00p.m. to 04.00p.m. on or before **01.02.2016**.

Estimated cost of work is **Rs.256301.00** Earnest money to be deposited amounting to **Rs.5,200/-** in cash or in the form of D.D./pay order of the schedule Bank in favour of **Executive Engineer, Central Warehousing Corporation, Kolkata** (payable at Kolkata).

Quotation not accompanied with the Earnest Money Deposit in Cash Receipt / in the form of Demand Draft/ Pay Order drawn in favour of **Executive Engineer, Central Warehousing Corporation, Kolkata**, shall be summarily rejected.

The quotationers are requested to quote the rate at page **No.9** on going through the schedule (enclosed) and the quotation duly completed with schedule of work under sealed envelop superscribing the name of work shall be submitted to the office of the **EXECUTIVE ENGINEER, CENTRAL WAREHOUSING CORPORATION, New Market Complex,CMC Building(6th floor),15N,Nellie Sengupta Sarani, Kolkata-700087** upto 15.00 hours on **03.02.2016** and the same will be opened at 15.30 hrs. on the same day in the presence of quotationers/contractors who may wish to be present at the time of opening.

The quotation papers can also be downloaded from the website www.cewacor.nic.in and www.tenderhome.com.

The Central Warehousing Corporation reserves the right to accept or reject all/any part of quotation without assigning any reason there-of.
Copy to

1. The Regional Manager,CWC, RO,Kolkata for information.
2. The A.E (E),CWC,CC, Kolkata.
3. The Sr.Asstt.Manager(A/Cs),CWC,CC, Kolkata.
4. The ASW,CWC,CC, Kolkata.
5. Warehouse Manager,CW,C.K.Road along with 5 copies of NIQ for wide publicity.
6. Notice Board of CC, Kolkata/RO Kolkata

EXECUTIVEENGINEER

EXECUTIVEENGINEER



CENTRAL WAREHOUSING CORPORATION
(A GOVT. OF INDIA UNDERTAKING)

NAMEOFWORK: Electrical Renovation work at CW, C.K.Road for the year 2015-16

SCHEDULE OF QUANTITY

SI No	DESCRIPTION	Quantity	UNIT	RATE	AMOUNT
1	Dismantling of existing aluminium wires from conduit , old rusted conduit from truss and office, damaged switches, switchgears etc as required from godown and office.	1.00	Each	3240.00	3240.00
2	Supplying and fixing of following sizes of pvc conduit alongwith accessories in surface /recesse including cutting the wall and making good the same in case of recessed conduit as required..	591.00 mtr	Mtr	47.00	27777.00
	a) 25 mm				
3	Supplying and drawing following size of FR PVC insulated copper conductor single core cable in the existing surface /recessed steel/pvc conduit as required.				
	a) 3x1.5 Sq.mm	184.00	Mtr	32.00	5888.00
	b) 4x1.5 sq.mm	137.00	Mtr	38.00	5206.00
	c) 5x1.5 sq.mm	103.00	Mtr	45.00	4635.00
	d) 6x 1.5 sq.mm	70.00	Mtr	52.00	3640.00
	e) 7x1.5 sq.mm	4.00	Mtr	58.00	232.00
	f) 3x2.5 sq.mm	84.00	Mtr	43.00	3612.00
	g) 3x4.0 sq.mm	144.00	Mtr	58.00	8352.00
4	Supplying and fixing of 12/13 mm flexible metal conduit including connection ,painting etc.on surface\recess as per direction of Engineer in charge.	16.00	Mtr	26.00	416.00

SI No	DESCRIPTION	Quantity	UNIT	RATE	AMOUNT
5	Supplying of industrial box type luminaire , prewired for LED - 1x16/18/20 watt tube having powder coated in white CRCA ,M.S. Box complete with all accessories and energy efficient 1x16/18/20 watt , 4 feet length (Make Crompton Cat: LT8-16/20W) LED tube as required .make Crompton Cat ref: IGP 131LT8-16 or equivalent in Bajaj/philips.	48.00	Each	1677.00	80496.0
6	Supplying and fixing following way three pole and neutral sheet steel MCB distribution board, 415 volts, on surface/recess , complete with tinned copper busbars, neutral bus bar , earth bar , din bar , detachable gland plate, interconnections , phosphatized and powder painted including earthing etc as required.(but with out MCB/RCCB/Isolator)				
	a) 4 way (4+12), double door horizontal type.	1.00	Each	1311.00	1311.00
7	Supplying and fixing following way single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/recess , complete with tinned copper busbars neutral busbar, earth bar , din bar detachable gland plate, interconnections , phosphatized and powder painted including earthing etc as required.(but without MCB/RCCB/ Isolator)				
	a) 8 way double door	3.00	Each	709.00	2127.00
	b) 12 way double door	6.00	Each	746.00	4476.00
8	Supplying and fixing following rating four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc as required.				
	a) 63 amps	1.00	Each	362.00	362.00
9	Supplying and fixing following rating double pole ,240 volts , isolator in the existing MCB DB complete with connection, testing and commissioning etc as required.				
	a) 40 amp.	3.00	Each	166.00	498.00
10	Supplying and fixing 5amps to 32 amps rating ,240 volts , 'B' series miniature circuit breaker suitable for lighting and other load of following poles in the existing MCB DB complete with connection, testing and commissioning etc as required.				
	a) Single pole	51.00	Each	86.00	4386.00

SI No	DESCRIPTION	Quantity	UNIT	RATE	AMOUNT
11	Supplying and fixing 20 amp.240 volts SPN industrial type socket outlet ,with 2 pole and earth , metal enclosed plug top along with 20 amp. 'C' series , SP, MCB in sheet steel enclosure on surface or in recess with chained metal cover for socket outlet and complete with connection , testing and commissioning etc. as required.	3.00	Each	520.00	1560.00
12	Supplying and fixing 3 pin 5 amp. ceiling rose on the existing junction box /wooden block including connection etc. as required	47.00	Each	19.00	893.00
13	Supplying and fixing G.I, pipe bracket (ISI) made out of class B ,40mm OD G.I.pipe upto 1.5 metres length along with 2 sets of suitable clamps, nuts & bolts including bending in shape, smoke grey painted with primer etc. as required.	4.00	Each	510.00	2040.00
14	Installation , testing and commissioning of prewired flourescent fittings/ compact flourescent fitting of all type complete with all accessories and tube etc. directly on ceiling/wall including connection with 1.5 sq. mm FR pvc insulated copper conductor single core cable and earthing etc. as required.	48.00	Each	43.00	2064.00
15	Supplying ,installation, testing and commissioning of 45 watt LED , pressure die cast aluminium housing, heat resistant toughened glass street light luminaries/ fitting, operating voltage 120-270 V A.C , IP 65/66 protection , light lumen more than 3500, life span of LED 50000 hrs, antiglare, driver etc. complete with all accessories .(Make Crompton Cat: NEXUS+ LSTO-45-CDL or equivalent in Bajaj Cat- BRTFG-45 watt LED, Philips	8.00	Each	8762.00	70096.00

SI No	DESCRIPTION	Quantity	UNIT	RATE	AMOUNT
16	Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface/recessed pvc conduit with Modular switch, modular plate, suitable size G.I. box and earthing the point with 1.5 sq.mm FR PVC insulated copper conductor single core cable as required. Gr-C	19.00	Each point	426.00	8094.00
17	Wiring for circuit /submain wiring along with earth wire with the following size of FR pvc insulated copper conductor single core cable in surface/recessed pvc conduit as required				
	a) 2 x 2.5 Sq.mm + 1 x 2.5 Sq.mm earth wire	35.00	Mtr	81.00	2835.00
	b) 2 x 4.0 Sq.mm + 1 x 4 Sq.mm earth wire	27.00	Mtr	97.00	2619.00
18	Supplying and fixing suitable size G.I. box with modular plate and cover in front on surface or in recess including providing and fixing 6 pin 5/6 amp.and 15/16 amp modular Socket outlet and 15/16 amp. modular switch, connection , painting etc. as required	3.00	Each	214.00	642.00
19	Supplying and fixing following modular switch/socket on the existing modular plate and switch box including connection but excluding modular plate etc. as required. a) 3 pin 5/6 amp socket outlet	5.00	Each	64.00	320.00
20	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connection but excluding modular plate etc. as required.	4.00	Each	247.00	988.00
21	Painting of ceiling fan in installed position with one or more coats of spray painting with synthetic enamel paint of approved brand and manufacture to give an even shade , including cleaning of surface with detergent etc. as required.	4.00	Each	44.00	176.00
22	Supplying, fixing ,testing and connection of 45 watt CFL Lamp on the existing Post to lantern on gate pillar with necessary holder etc. as required as per direction of Engineer in-charge.	2.00	Each	424.00	848.00

SI No	DESCRIPTION	Quantity	UNIT	RATE	AMOUNT
23	Supplying and fixing 7 watt LED lamp including angle holder with connection etc. as required (make philips/NTL pharox)	6.00	Each	523.00	3138.00
24	Repairing of existing Flood light luminaires with providing 250 watt MV copper choke, 250 watt MV lamp, (make Philips/Bajaj/Crompton) holder, testing connection with copper wire etc as required (including credit value to old existing copper choke)	2.00	Sq.m	1667.00	3334.00

Total estimated cost of item from S.No 1 to 24 Rs 256301.00

(Rupees three lakh forty seven thousand eight hundred sixty three only)

CREDIT ITEM :-

sl	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Credit value for old damaged entire dismantled aluminium wires, from Godown. and office Building, dismantled switch gears in godown , tube light box (LS-as available in Godown and office), switches (as available), MCB(LS-), MCBDB- and rusted/damaged MS switch boxes etc. rusted conduit in office as available.	1.00 L.S	L.S	5120.00	5120.00

Total credit value:

Rs.5120.00

Note:

1. No enhancement/abatement will be allowed on the Credit value Item.
2. The Total amount will be recovered in 1st R/A bill.
3. The contractor will be allowed to take out the dismantled materials on full recovery of credit value.

EXECUTIVE ENGINEER

TERMS & CONDITIONS:

1. Works should be executed as per CPWD specifications.
2. Water & Electricity will be arranged by the contractor at his own cost.
3. All T&P required for the work shall be arranged by the contractor at his own cost.
4. The rates are inclusive all lead & lifts etc.
5. All taxes Income Tax, Work contract Tax (except service tax) as applicable will be deducted as per Govt.Rule from the contractor bill.
6. 10% S.D will be deducted from the gross bill amount & will be released after the defect liability period of six months which will be reckoned from the date of successful completion of the work. In case any defect is found in the said work within the defect liability period, the same shall be rectified by the contractor immediately at his own cost.
7. Contractor will be fully responsible to labour payments, accident, mis-happening, damages & other labour welfare & safety measures.
8. Time allowed for completion of work is 60(sixty) DAYS from the date as to be mentioned in Work Order.
9. The above shown quantities are tentative & may vary as per site condition.
10. All payments will be released through e-payments by CC,Kolkata.
11. SalesTax or any other tax on material as promulgated by Govt.of India from time to time in respect of this contract shall be payable by the contractor and Central Warehousing Corporation will not entertain any claim whatsoever in this respect.
12. The rates shall be quoted exclusive of Service Tax or any other Tax levied by the Central Government in lieu of Service Tax and the same will be payable by the Corporation over and above the Schedule of Rates.
13. In the event of any of the documents found fabricated /forged /tampered / altered / manipulated in the NIO, then the EMD of the contractor would be forfeited and he would be debarred for participating in CWC –tendering for 5 years.
14. The party to whom the work will be awarded will execute a formal agreement with CWC on a non-judicial stamp paper of appropriate value.
15. The Copy of PAN CARD and Service Tax Registration, along with quotation/ tender document shall be submitted.
16. The validity of Quotation will remain in force for 60 (sixty) days from the date of opening of quotation.

EXECUTIVEENGINEER**SIGNATUREOF CONTRACTOR**

UNDERTAKING

I/We _____
(Name of the Tenderer with address) have been doing the works for the Government Department/Central PSUs/State PSUs for the last _____ years and I/we certify that I/We have never been blacklisted /debarred by any of the Government Department/Central PSUs/State PSUs on account of any of the default on our part in execution of the projects/works. I/We also undertake to mention that if at any point of time it comes to the notice of CWC that the above undertaking given by Me/Us is false than CWC will be at liberty to forfeit our EMD/security Deposit and also to terminate the contract.

Name of Contractor with address



Name of work: Electrical Renovation work at CW, C.K.Road for the year 2015-16

Estimated cost from Item No.1 to 24 Rs. 2,56,301.00(Rupees two lakh fifty six thousand three hundred one) only.

a) I/We here by tender our rates as _____%
(_____Percent) ABOVE the rates entered
in the schedule of quantities from item No.1 to 24

OR

b) I/We here by tender our rates as _____%
(_____Percent) BELOW the rates entered
in the schedule of quantities from item No.1 to 24.

Note: The Quotationers should quote their percentage appropriately either at (a) or (b) as the case may be.

**Executive Engineer
CWC, CC-Kolkata**

Signature of Contractor.