CENTRAL WAREHOUSING CORPORATION
(A GOVT. OF INDIA UNDERTAKING)

Regional Office, Scope Minar, Core-3, Ist Floor, Laxminagar Distt. Centre, Delhi-110092

No. CWC/RO-DLI/Engg. Section/NIQ/2019-20/2862 **Dated 06/09.12.2019**

NOTICE INVITING QUOTATION
(E-tendering mode only)

Online percentage rate E-quotation is invited in two bid system for the below mentioned works from Contractors of appropriate class of CPWD/Railways/MES/State PWD/other Government Organization/ Public Sector Undertakings & their Subsidiaries or having worked/ working with aforesaid Government Departments/ Agencies:-

Name of Work	**Raising Boundary Wall height of front and rare side, including cement plaster of Boundary wall at CW, R.P. Bagh, Delhi.**
Estimated cost put to NIQ	**Rs.8.81 Lakh**
Earnest Money	**Rs.18,000.00**
Time Allowed for completion of work	**Two Months**
Last date & time of download of NIQ	**26.12.2019** upto 15:00 Hrs.
Last date & time of submission of Quotation	**26.12.2019** upto 15:00 Hrs.
Date & time of opening of Quotation	**27.12.2019** 15:30 Hrs.

Quotation documents with contract conditions and schedule of work may be down loaded by the intending contractors, who wish to participate, from **CWC website www.cewacor.nic.in or e- tenderwebsite www.cwceprocur.com/CWC or CPP Portal http://eprocure.gov.in/epublish/app up to 26.12.2019 at 15:00 Hr.**

CENTRAL WAREHOUSING CORPORATION
(A Govt. of India Undertaking)

SCHEDULE OF QUANTITY

Name of Work :- **Raising Boundary Wall height of front and rare side, including cement plaster of Boundary wall at CW, R.P. Bagh, Delhi.**

S. No.	Item	Unit	Qty.	Rate	Amount
1.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar (1 cement : 4 coarse sand)	Cum	26.60	4970.30	132209.98
2.	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	7.00	7390.80	51735.60
3.	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	57.20	342.90	19613.88
4.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg.	563.00	56.60	31865.80
5.	CEMENT PLASTER (IN FINE SAND) 12 mm cement plaster of mix : 1:4 (1 cement : 4 fine sand)	Sqm	1914.00	172.95	331026.30
6.	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	Sqm	110.00	200.25	22027.50
7.	20 MM CEMENT PLASTER 1:4 (1 cement : 4 fine sand)	Sqm	800.00	240.15	192120.00
8.	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	Sqm	90.09	143.80	12954.94
9.	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick)	Mtr.	143.00	255.00	36465.00

	wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)				
10.	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	630.00	67.60	42588.00
11.	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:1½:3 (1 cement : 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	0.79	6990.40	5522.42
12.	Neat cement punning.	Sqm	33.00	42.60	1405.80
13.	Dismantling angle iron post and barbed wire from boundary wall and stacking the material safety within 50 mtr. Lead.	Each	60.00	30.00	1800.00
	TOTAL				**881335.22**

(Rupees Eight lakh eighty one thousand three hundred thirty five and paise twenty two only)

(EXECUTIVE ENGINEER)

TERMS AND CONDITIONS

1. Quotationer/bidder should have been registered with CPWD/Railways/MES/State PWD/other Government Organization/ Public Sector Undertakings & their Subsidiaries or having worked/ working with aforesaid Government Departments/ Agencies.

2. Security Deposit will be deducted @10% of gross amount of bill of the contractor which will be refunded after successful completion of defect liability period of 6 months. In case any defects are found within defect liability period, the same shall be repaired by the Contractor immediately at his own cost. EMD deposited alongwith the quotation shall be adjusted against the security deposits to be deducted from the bills of the contractor.

3. Quotationers/bidders should have completed successfully at least one similar nature of work " **i.e any Civil engineering works"** of value not less than **Rs.3.09 Lakh/-.** during the last four financial years (i.e. 2015-16, 2016-17, 2017-18 & 2018-19) and current year (2019-20) up to the date of tender submission. **Note: It should be noted that credentials for the works executed for Private Organisations shall not be considered.**

4. The sum total (arithmetic sum) of quotationers turnover/revenue (income) from operations for the last three financial years (i.e. 2016-17, 2017-18 & 2018-19) should be of value not less than **Rs.7.94 Lakh/-.** The information shall be supported by CA certificate & audited Balance Sheets and of Profit & Loss Statements of specified last three financial years. In case Balance Sheet and Statement of Profit & Loss for the immediate preceding financial year have not been prepared/audited, the account for one more preceding financial year can be submitted.

5. Necessary taxes i.e. -Income Tax & other statutory taxes levied by Govt. time to time will be deducted from the bill as per prevalent rate as on date.

6. Quotationers/bidders shall quote their rates inclusive of GST, as applicable and GST will not be paid/reimbursed by CWC.

7. GST, Building or other construction workers cess or any other tax, levies, duties on materials and on complete works in respect of this contract shall be payable by the contractor and CWC will not entertain any claim what so ever in this respect. This should be included in the rates quoted by contractor.

8. The contractor shall be required to pay labour cess @ 1% of cost of construction work in accordance with each bill payable on account of such construction to the concerned State of Govt. (Labour Deptt.) Cost of material shall be outside the purview of cess, when supplied under a separate schedule items. CWC shall not entertain any claim whatsoever in this respect.

9. Contractor will have to arrange all labour, T&P etc. (at all levels) required for the execution/completion of the work as per site condition. Safety of working labour's lies on contractor only at all levels.

10. Items & Quantities given in the schedule are tentative to give an idea of work involved which may vary as per actual execution at site.

11. Work shall be executed strictly as per CPWD specification/Schedule. Work is to be completed within **Two Months** from the date of issue of work order.

12. The Contractor will sign each paper of Quotations in token of acceptance of their offer.

13. The offer rate shall be valid for 60 days from the date of opening of quotations.

14. The time for execution of the work specified in the work order shall be deemed to be essence of the contract and the work must be completed within the specified period. If the contractor fails to complete the work within the specified period mentioned in the work order, the Competent Authority may at his discretion extend the date of completion and also consider levy of penalty as deemed fit based on the merit of the case.

15. In the event of any documents found forged/fabricated/tampered/ altered or manipulated, then the EMD of the Contractor would be forfeited and he would be debarred for participating in CWC for 5 years.

16. If, the work is not started by the contractor within 1/8th of stipulated time.

Or

The contractor having been given a notice in writing to rectify, reconstruct or replace any defective work or fails to complete the work within the stipulated date or persistently neglects to carry out his obligations under the contract and does not remedy it or take effective steps within 7 days after the notice, the Engineering-in-Charge shall have power to rescind the contract and the EMD, security deposit already deducted under the contract shall be liable to the forfeited.

17. No advance payment shall be made at any time and payment shall be made only after execution of items/work.

18. Before quoting the rates, contractor may visit the site.

19. The Contractor shall not sublet/assign the contract work to any other contractor.

20. The contractor will have to abide by the labour laws and have to extend the statutory due benefit to the person deployed and the CWC will not be held responsible for any compensation in case of any mis-happening during contract period.

21. Contractors submitting bid on behalf of a firm/Company must submit partnership deed or Certificate of Incorporation of the Company and Power of Attorney in the name of person signing the tender/quotation.

22. It is a works contract and there is no EMD exemption on account of MSME.

23. Contractor will upload the bank details (cancelled cheque).

24. CWC reserves the right to accept or reject any or all the quotations without assigning any reason thereof.

Note:- For deciding eligibility of NIQ, it is, mandatory for the bidder to submit Financial turnover (Balance sheets with profit & loss account of specified proceeding three years as per NIQ, similar nature of work experience certificates of requisite magnitude as per NIQ, failing which the quotation shall be summarily rejected.

Contractor **Executive Engineer**

PERFORMA FOR QUOTING THE RATES

Name of the Work : Raising Boundary Wall height of front and rare side, including cement plaster of Boundary wall at CW, R.P. Bagh, Delhi.

Estimated cost as per **Item No.01 to 13 of Rs.881335.22** (Rupees Eight lakh eighty one thousand three hundred thirty five and paise twenty two only)

I/We hereby quote our rates as ……%(……Percent)

ABOVE the rates entered in the schedule of quantities.

OR

I/We hereby quote our rates as ……%(…… …..Percent)

BELOW the rates entered in the schedule of quantities.

Contractor,s Signature & Address **Executive Engineer**

Annexure-'A'

UNDERTAKING

I /We _____ (Name of the quotationer with address)_____ have been doing the works for the Govt. Department / Central PSUs/ State PSU/ Private organizations for the last _____ years and I/We have never been blacklisted / debarred by any Govt. Department / Central PSUs/ State PSUs or Private organization on account of any default on our part in execution of the projects / works.

I /We also undertake to mention that if any any point of time it comes to the notice of CWC that the above undertaking given by me / us is false then CWC will be at liberty to forfeit our EMD/Security Deposit and also to terminate the contract.

Name of Contractor with address