CENTRAL WAREHOUSING CORPORATION

(A GOVT. OF INDIA UNDERTAING)

Name of work : Providing Passenger Lift for office building at R.O. Vibhuti Khand, Gomti Nagar, Lucknow.

SCHEDULE OF QUANTITIES

Sr.	Description of work	Qty.	Unit	Rate	Amount
1	**PASSENGER LIFT** Supplying, installation, testing and commissioning of 08 Passenger (544 Kg.) having contract speed of 1 mps, serving different floors in the lift shaft as per detailed specification enclosed and as under : **Make OTIS/ KONE / SCHINDER/ MITSUBISHI/ JOHNSON LIFTS** a. Speed -1.0 MPS b. Floor-4 floors (G+3) c. Travel-13.6 meters(Approx) one way. d. No. of stops and opening-04. e. Controller-AC VVVF f. Automatic Rescue Device completes with dry maintenance free batteries as required. g. Infra red curtain for door as required. h. Operation: Microprocessor based simplex selective collective with or without attendant. i) Power: 415 volts,3phases,50 Hz, AC supply. ii) TYPE OF DOOR: Car: Power operated opening, Centre opening stainless hairline finish. iii) Landing Doors: Centre opening ,centre opening stainless steel mirror finished. iv) **Car panels**: Stainless steel mirror finished. v)Handrails on three sides of the car at 900 mm above floor level. vi) wall moulting lop & cop.	01	each	1450000	1450000

EXECUTIVE ENGINEER