



CENTRAL WAREHOUSING CORPORATION

(A Govt. Of India Undertaking)

QUOTATION DOCUMENT

NAME OF THE WORK: - Urgent repairs work to valley gutters, construction of retaining wall and installation of Bio-toilet at CW, Maligaon.

REGIONAL OFFICE, GUWAHATI.

Issued to:

.....
.....
.....
.....



CENTRAL WAREHOUSING CORPORATION
(A Govt. of India Undertaking)

Regional Office: 39, Sapta Swahid Path, Sarumotoria, Dispur,
Guwahati-781006



CWC RO-GHYOENGG/6/2023-ENGG_GHY

Date: 20.03.2023

NOTICE INVITING QUOTATION

NAME OF WORK: Urgent repairs work to valley gutters, construction of retaining wall and installation of Bio-toilet at CW, Maligaon.

Sealed percentage rate quotations are invited from the contractors in appropriate class. The quotation papers may be had from the office from THE ASSISTANT ENGINEER, CENTRAL WAREHOUSING CORPORATION, 39, Sapta Swahid Path, Sarumotoria, Dispur Guwahati – 781006 in working hours from 14:59 on or before **25.03.2023**.

Estimated cost of work is **Rs.6,54,298.13**, Earnest money to be deposited amounting to **Rs.13,100/-** in the form of D.D./Online Transfer (**Bank Details is Enclosed**) from the schedule Bank in favor of THE REGIONAL MANAGER, CENTRAL WAREHOUSING CORPORATION, GUWAHATI

The quotationers are requested to quote the rate in schedule of work and the same/quotation duly completed schedule of work under sealed envelope super scribing the name of work shall be submitted to the **ASSISTANT ENGINEER, CENTRAL WAREHOUSING CORPORATION, 39, SAPTASWAHIDPATH, SARUMOTORIA, DISPUR GUWAHATI-781006** upto 15.00 hours on **25.03.2023** and the same will be opened at 15.30 hrs. On the same day in the presence of quotationers/contractors who may wish to be present at the time of opening.

The quotation papers can also be downloaded from the website
www.cewacor.nic.in and www.tenderhome.com

The Central Warehousing Corporation reserves the right to accept or reject all/any part of quotation without assigning any reason there-of.

ASSISTANT ENGINEER

Copy to:

1. The Regional Manager, CWC, RO, Guwahati.
2. The AGM (A/Cs), CWC, CC, Guwahati.
3. The Warehouse Manager, CW, Maligaon.
4. Notice Board of RO Guwahati/CW Maligaon.

CENTRAL WAREHOUSING CORPORATION
(A GOVT. OF INDIA UNDERTAKING)
Schedule of Quantity

NAME OF WORK: Urgent repairs work to valley gutters, construction of retaining wall and installation of Bio toilet at CW, Maligaon.

SL	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (a)In cement mortar	0.54	cum	1698.45	917.16
7	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	34.43	Kg.	3.20	110.18
3	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet	115.21	sqm	136.00	15668.56
4	Providing valleys of 104cm wide overall in plain G.S. sheet fixed with polymer coated J, or L hooks, bolts and nuts 8mm dia.. G.I. limpet and bitumen washers complete. 1.40mm thick with zinc coating not less than 350gm/m ²	129.38	meter	1,660.74	214866.64
5	Providing flat iron brackets 50x3mm size with necessary bolts, nuts and washers etc. for fixing asbestos cement/G.S. sheets gutters with purlins.	48.66	meter	77.00	3746.82
6	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand)	0.27	cum	8,512.10	2298.27
7	15 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand)	2.23	sqm	339.70	757.53
8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains	6.00	Cum	205.45	1232.70
9	Providing and laying in position cement concrete of specified g- All work up to plinth level :1:5:10	1.00	Cum	6,050.65	6050.65

10	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	22.50	Cum	8,364.20	188194.50
11	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	68.00	Sqm	804.25	54689.00
12	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete up to plinth level, Thermo Mechanically treated bars of grade Fe- 500D or more	808.09	Kg	89.65	72445.17
13	12 mm cement plaster of mix :(a)1:4 (1 cement : 4 coarse sand)	55.20	Sqm	307.25	16960.20
14	White washing with lime to give an even shade :New work (two or more coats) with a base coat of white washing with lime	55.20	Sqm	32.45	1791.24
15	Providing and Installation of Bio toilet with all item including	1.00	No's	74569.51	74569.51
Total Estimated Cost Rs.					6,54,298.13
(Rupees Six Lakh Fifty Four Thousand Two Hundred Ninety Eight & Paise Thirteen Only)					

ASSISTANT ENGINEER

TERMS & CONDITIONS:

1. Works should be executed as per CPWD specifications.
2. Water & Electricity will be arranged by the contractor at his own cost.
3. All T&P required for the work shall be arranged by the contract or a this own cost.
4. **The rates are inclusive GST and all lead & lifts etc.**
5. All taxes Income Tax, Work Tax etc (except service tax) as applicable will be deducted as per Govt. Rule from the contractor bill.
6. **10% Security Deposit will be deducted from the gross bill amount & will be released after the defect liability period of six months which will be reckoned from the date of successful completion of the work. In case any defects found within the defect liability period, the same shall be repaired by the contractor immediately at his own cost.**
7. **Contractor will be fully responsible to labor payments, accident, miss happening, damages & other labor welfare & safety measures.**
8. Time allowed for completion of work is 2(Two) Months, from the date as to be mentioned in the work order.
9. The above shown quantities are tentative & may vary as per site condition.
10. All payments will be released through e-payments by RO, Guwahati.
11. GST and other taxes on material as promulgated by Govt. of India from time to time in respect of this contract will be deducted by the contactor.
12. The rates quote dare inclusive of GST or any other Tax levied by the Central Government in lieu of Service Tax and the same will deducted by Corporation on Schedule of Rates.
13. In the event of any of the documents found fabricated / forged / tampered / altered /manipulated in the NIQ, then the EMD of the contractor would be forfeited and he would be debarred for participating in CWC-tendering for 5years.
14. The voucher for Cement, paint, Bitumen & Steel should be produced while submitting the bills.
15. The parties to whom the work will be awarded will execute a formal agreement with CWC on a non-judicial stamp paper of appropriate value.
16. The steel for reinforcement shall be arranged by the contractor from BIS license holder manufacturer.
17. Payment against steel items shall be made on practical or theoretical weight or physical whichever is less.
18. Cement to be used in the work would be PPC in conformity with the relevant B.I.S codes and should be arranged by the contractors from major producers.
19. In the event of failing to execute the work within quoted rate the EMD of contractor would be forfeited & he would be banned for a period participating of 5 years in CWC tender/quotation.
20. Copy of self-attested PAN CARD, GST, and contractor license and experience certificate of the work done in Civil Works shall be submitted along with the quotation.
21. The rate quoted will remain valid for 60days w.e.f date of opening of bid.

ASSISTANT ENGINEER

SIGNATURE OF CONTRACTOR



**CENTRAL WARE HOUSING CORPORATION
(A GOVT. OF INDIA UNDERTAKING)**

NAME OF WORK: - Urgent repairs work to valley gutters, construction of retaining wall and installation of Bio-toilet at CW, Maligaon.

ESTIMATED COST/SCHEDULE OF QUANTITIES

FROM ITEM NO.01 to 15=Rs.6, 54,298.13

a) I/We here by tender our rates as _____%
(_____Percent) **ABOVE the** rates entered in the schedule of quantities from item No.01 to15.

OR

b) I/We here by tender our rates as _____%
(_____percent)**BELOW the** rates entered in the schedule of quantities from item No.01 to15.

Note:

1. Quotations should quote their percentage appropriately either at (a) or (b) as the case may be.
2. No enhancement or abate mentis applicable or credit value item.

SIGNATURE OF CONTRACTOR

ASSISTANT ENGINEER

BankDetails

 सेन्ट्रल बैंक ऑफ इंडिया Central Bank of India	सिक्स माइल्स, जी.एस. रोड, जिला कामरूप, असम SIX MILES, G.S. ROAD, DIST. KAMRUP, ASSAM-781022 IFSC: CBIN0284213	सभी शाखाओं पर देय PAYABLE AT ALL BRANCHES दि दि मा मा व व व व D D M M Y Y Y Y
	Pay _____ या धारक को or Bearer	रुपये Rupees _____
खाता सं. A/c. No.	3314879845	
SIXMIL	CENTRAL WAREHOUSING CORPORATION (RM OPERATIONAL A/C) GUWAHATI PABAN DE SATRUGHAN RAJBHAR	कृपया हस्ताक्षर ऊपर करें / Please sign above

1102909611 7810160241: 00075211 29